

**MGM College of Engineering  
and Technology,**

Plot No. 1 & 2, Sector-1,  
Kamothe, Navi Mumbai- 410209

**TENDER NOTICE**

Tenders are invited under  
e-Tendering System from  
Reputed Manufacturers /  
Agencies / Distributors for  
**purchase of UPS and batteries**

for Engineering College,  
Sector 1, Kamothe,  
Navi Mumbai, as published in  
website: [www.mgmmumbai.ac.in](http://www.mgmmumbai.ac.in)

The lowest quotations  
should be emailed at :  
[etenders@mgmmumbai.ac.in](mailto:etenders@mgmmumbai.ac.in)  
before 4.00 pm on Monday.

**Date: 29.06.2026**

**Director**

**3 (W) x 6 (H)**

**Note:**

Kindly email your latest Quotation along with all Terms and Conditions, Authorization letter, Catalogs, Client list with installation year and their contact details. Submit only on e-mail:- [etenders@mgmmumbai.ac.in](mailto:etenders@mgmmumbai.ac.in) before 4:00pm on 29<sup>th</sup> June 2026.

MGM CET reserves the right to reject any or all tenders without assigning any reason thereof.

**Director  
MGM CET, Navi-Mumbai.**

**75 KVA Online Modular UPS Purchase – BOQ & Quotation Format with following Specifications:**

Project: Supply, Installation, Testing & Commissioning of 75 KVA Online Modular UPS System

**Location: MGM CET, Kamothe, Navi Mumbai.**

**Recommended UPS Make**

**1) Ador 2) Eaton 3) Fuji Electric 4) APC**

Sr. No.	Description	Unit	Qty
1	75 KVA Online Modular UPS, 3 Phase In/Out	No's	2
2	Parallel Redundancy	No's	1
3	SMF VRLA Quanta Battery 12V, 100 Ah	Set	
4	Battery Rack: Heavy Duty MS Rack	Set	2
5	UPS Input & Output MCCB with Enclosure and Cables	Set	Not Required
6	Battery Interconnecting Cables, Lugs with Uninyvin cable	Set	Required
7	Installation, Testing & Commissioning	Job	1
8	Training & Documentation	Job	1
9	Warranty for UPS	3 Years	1
10	Warranty for Batteries	2 Years	1
12	Transportation & Delivery	Required	1
13	Delivery Period	Job	15 to 20 days After PO.
14	Batteries Backup Time on 100% Load 30 to 45 Minutes for Each UPS	Job	Required
15	PPM During Warranty Period	Job	Quarterly
16	Hot Swappable	Job	Required
17	Efficiency	Job	≥95%
18	MCCB & Accessories for Batteries Breaker	No's	2
19	UPS I/P & O/P Maintenance bypass / batteries Isolation Breaker	No's	Required
20	UPS Test Certificate	Job	Required
21	UPS Trouble Shooting Chart	Job	Required
22	LCD Display for Monitoring and Maintenance	Job	Required
23	Overload Short Circuit protection	Job	Required
24	Advance / Latest Technology True Online Double Conversion UPS	Job	Required
25	Output Power Factor 0.9	Job	Required
26	THD: < 2% at Non-Linear Load	Job	Required
<b>Over Load Capacity</b>			
27	125 % Load	Job	10 Minutes
28	150 % Load	Job	60 Seconds
29	175 % Load	Job	10 Seconds